4	KSRRB M400-14.1: Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specifications including spreading in uniform thickness, hand packing, rolling with 3 wheeled steel/vibratory roller 8-10 tonnes in stages to proper grade and camber, applying and brooming requisite type of screening/binding Materials to fill up the interstices of coarse aggregates, watering and compacting to the required density Complete as per Specification. A. By manual means. MORTH Specification No. 404 Type A 13.2mm for grading II Page No. 167/ Item No. 20.14.1/ PWD SR 2012-13	Cum							
			1	145.00	4.50	0.15	97.88		
			1	182.00	4.80	0.15	131.04		
	Basic Rate	1200.00					**228.92**	1296.00	**296674.00**
	Area Weightage 8%	96.00							
	Total	**1296.00**							
5	KSRRB M400-14.2: Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with 3 wheeled steel/vibratory roller 8-10 tonnes in stages to proper grade and camber, applying and brooming requisite type of screening/binding Materials to fill up the interstices of coarse aggregate, watering and compacting to the required density Complete as per Specification. B. By Mechanical means. MORTH Specification No. 404 Type B 11.2mm for grading III Page No. 167/ Item No. 20.15.3/ PWD SR 2012-13	Cum							
			1	145.00	4.50	0.10	65.25		
			1	182.00	4.80	0.10	87.36		
							152.61	1364.04	**208166.00**
	Basic Rate	1263.00							
	Area Weightage 8%	101.04							
	Total	**1364.04**							
6	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 10 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading Item No. 17.1 KSRRB M 100-1 Rs. 62.20 (P.147 I.18.57/1)	Cum							
	Qty Vide Item No=1						**599.93**		
	Qty Limited to						**599.93**	100.35	**60205.00**
	Basic Rate	25.60							